

# Brown & Mitchell, Inc.

Consulting Engineers  
Gulfport, MS — Biloxi, MS

January 19, 2010

## ADDENDUM NO. 3

### JONES PARK IMPROVEMENTS, PHASE 2 JONES PARK DRIVE & 20TH AVENUE

This Addendum is hereby made a part of the Contract Documents to the same extent as though it were originally included therein. Receipt of this Addendum must be acknowledged in the Bid.

Listed below are the revisions and clarifications which are referenced to the designated locations in the Specifications and Construction Plans:

1. Contract Documents, Bid Proposal (Addendum No. 1), Pages BP-1 through BP-20 – Delete the Bid Proposal transmitted in Addendum No. 1 and replace with the attached Bid Proposal (Addendum No. 3) in its entirety.
2. Technical Specifications, Section 02234 – Delete this section in its entirety and replace with the attached revise Section 02234 (Addendum No. 3).
3. Technical Specifications, Section 02521, Page 02521-4, Subparagraph 5.1 – Delete “02521-E Rollover Curb, Type 3 \$ \_\_\_\_\_ per linear foot” from the list of pay items.
4. Technical Specifications, Section 02585, Page 02585-2, Paragraph 4.5 – Delete in its entirety and replace with the following:  
  
“4.5 Street Name Signs shall be measured by the square foot in accordance with Paragraph 4.1”
5. Technical Specifications, Section 16120, Page 16120-4 – Delete Part 4 and Part 5 in their entirety and replace with the following:  
  
“PART 4 – METHOD OF MEASUREMENTS  
  
A. Complete and accepted wire and cable will be measured for payment by the linear foot (single wire) as noted in the next section, Part 5.  
  
PART 5 – PAYMENT  
  
A. Payment will be made in accordance with Pay Item No.

Addendum No. 3 - 1  
09-3204A-02

16120-A #4 AWG Wire, XHHW-2  
(Jones Park Drive)  
\$ \_\_\_\_\_ per linear foot

16120-B #4 AWG Wire, XHHW-2  
(20th Avenue)  
\$ \_\_\_\_\_ per linear foot"

6. Technical Specifications, Section 16130, Page 16130-5 – Delete Part 4 and Part 5 in their entirety and replace with the following:

"PART 4 – METHOD OF MEASUREMENT

- A. Complete and accepted raceways, systems, boxes, etc., for a complete operational system, will be measured for payment by the linear foot and by the size of conduit as noted in the next section, Part 5. Raceways include but are not limited to, installation, supports, boring, trenching, backfill, restoring of sod, sidewalk, curbs and gutters, and any other impacted structure to its original condition.
- B. Concrete used for duct banks will be measured by the cubic yard.
- C. Pull Boxes will be measured as a unit, per each.

PART 5 – PAYMENT

- A. Payment will be made in accordance with Pay Item No.

16130-A 2" Rigid, Non-Metallic Conduit  
(PVC, Including Fittings and  
Accessories, Jones Park Drive)  
\$ \_\_\_\_\_ per linear foot

16130-B 4" Rigid, Non-Metallic Conduit  
(PVC, Including Fittings and  
Accessories, Jones Park Drive)  
\$ \_\_\_\_\_ per linear foot

16130-C 6" Rigid, Non-Metallic Conduit  
(PVC, Including Fittings and  
Accessories, Jones Park Drive)  
\$ \_\_\_\_\_ per linear foot

16130-D	1½" Rigid, Non-Metallic Conduit (PVC, Including Fittings and Accessories, 20th Avenue)	\$ _____	per linear foot
16130-E	Concrete (Duct Bank, Jones Park Drive)	\$ _____	per cubic yard
16130-F	Pull Boxes (Jones Park Drive)	\$ _____	per each"

7. Technical Specifications, Section 16490, Page 16490-3 – Delete Part 5 in its entirety and replace with the following:

PART 5 – PAYMENT

- A. Payment will be made in accordance with Pay Item No.

16490-A	Circuit Breakers and Fuses (20 A, 2 Poles, 208V) (Jones Park Drive)	\$ _____	per each
16490-B	Circuit Breakers and Fuses (20A, 2 Poles, 208V) (20th Avenue)	\$ _____	per each"

8. Construction Plans, Sheet G-1.0 – Add the following note:

"22. All references to "LIMESTONE" or "CRUSHED LIMESTONE" shall also mean "CRUSHED CONCRETE". Either material may be used at any location of the project with the exception of the LIMESTONE SURFACE TRUCK/TRAILER parking area, which may be only limestone."

9. Construction Plans, Sheet C-8.1 – Change label of "ROLL-OVER CURB & GUTTER" to "MOUNTABLE CURB & GUTTER". There will be no Roll-over Curb & Gutter or Rollover Curb, Type 3.

10. Construction Plans, Sheet E-7.0 - The contractor shall provide an additional 805 feet of 2-#4, 1-#4G conductors in 1-1/2" Schedule 40 PVC conduit and 330 feet of 4-#4, 1-#4G conductors in 1-1/2" Schedule 40 PVC for the extension of circuit numbers 17, 19 23, 24, 25, and 26 of temporary loadcenter LP to the permanent panelboard location. Loadcenter LP shown as "temporary" on the drawings may not be required if work under a separate contract, which includes the permanent panelboard, proceeds in a timely manner. Refer to section 16120 and 16130 of the specifications for conduit and wire requirements.

BROWN & MITCHELL, INC.

By: Dax Alexander  
Dax Alexander, P.E.  
President

